

Public Informational Meeting – February 15, 2024

Weirs Boulevard over Langley Brook
Laconia, NH
NHDOT Bridge # 135/128



Presentation Outline



- Introduction
- Presentation Goals
- Public Outreach (Prior Meeting)
- Purpose and Need
- Project Phases
- Project Alternatives
- Schedule
- Feedback/Comments



Introduction



- Project Team
 - City of Laconia (Owner)
 - NHDOT & FHWA (Funding Agencies)
 - Hoyle, Tanner & Associates, Inc. (Consultant)
- Hoyle Tanner Team
 - Josif Bicja, PE – Project Manager
 - Katelyn Welch, PE – Project Engineer



Presentation Goals



- Make Public Aware of Project Early in Design Process
- Share Project Development Process/Alternatives
- Listen to Concerns
- Gather Public Input
- Answer Your Questions



Public Outreach – Sept. 13 Meeting




- Local Concerns Meeting on September 13, 2023
 - Access to all Residential Areas During Construction
 - Access to nearby residences will be maintained at all times
 - Bike Lanes
 - Not part of this project
 - Require 24/7 Construction Activities
 - No weekend or night work will be allowed, unless an emergency
 - Erosion Control Measures During Construction
 - Contractor will be required to install and maintain



Public Outreach – Sept. 13 Meeting



- New Bridge Width
 - New bridge will match existing bridge width



Public Outreach – Sept. 13 Meeting



- Emergency Vehicles Impact
 - Access on each approach will be maintained. Detour route plans will be provided to Fire, Police & Ambulance.
- Need for Temporary and Permanent Easements
 - May be required. Will be coordinated during preliminary design. Individual meetings with affected abutters.
- Remove Silt Downstream of Bridge
 - Not part of this project
 - Goal of this project is to address bridge's deteriorated condition



Purpose and Need




- Purpose
 - Provide structurally cost-effective, safe bridge, which accommodates design floods, provides adequate load carrying capacity and rail system to improve roadside safety.
- Need
 - Provide access for residents and emergency response vehicles.
 - Improve the roadway safety, load carrying capacity, and hydraulic capacity.




Project Phases



- Preliminary Engineering
 - Engineering Study 
 - Preliminary Design
 - Permitting/ROW
 - Final Design
 - Bid Phase
- Construction
 - Construction
 - Construction Engineering



Project Alternatives



Project Alternatives – Existing Conditions



- Original Structure Built circa 1898, Widened in 1933, and Rehabilitated in early 1980s
- 26' Wide Travelway, 62' Wide Structure, 10' Span
- Superstructure
 - Partial Jack Arch (original)
 - Partial Concrete Slab (widening)
- Exposed Curb Reinforcing, Section Loss in the Jack Arch



Project Alternatives – Existing Conditions



- Substructure
 - Partial Stone Masonry (original)
 - Partial Concrete (widening)
- Cracks, Rust Staining, and Efflorescence of the Abutments
- Large Wingwall Spalls
- 10,202 Vehicles/Day (2021)



Project Alternatives – Existing Conditions



Project Alternatives – Existing Conditions




Project Alternatives



- Alternative No. 1 – “No Build”
- Alternative No. 2 – Rehabilitation
- Alternative No. 3 – Replacement
 - No. 3A – Precast Concrete Box Culvert
 - No. 3B – Precast Concrete Rigid Frame



Project Alternatives – Box Culvert




Project Alternatives – Box Culvert



North Shore Road
Derry, NH



Project Alternatives – Rigid Frame



Project Alternatives – Rigid Frame



Cider Mill Road
Bedford, NH



Project Alternatives – Cost Estimates



- Alternative No. 3 – Replacement
 - **\$2.9 M** (No. 3A – Precast Concrete Box Culvert)
 - **\$3.2 M** (No. 3B – Precast Concrete Rigid Frame)
- NHDOT Estimate = \$2.9 M



Project Alternatives – Recommendation




- No. 3A – Precast Concrete Box Culvert
 - 14' Clear Span
 - Two travel lanes and two shoulder that match existing widths
 - 63' overall width
 - NHDOT T2 steel rail




Project Alternatives – Rendering



Project Alternatives – Bridge Section



Project Alternatives – Roadway Plan





Project Alternatives – Detour Route

Project Schedule



- Engineering Study
 - February 2024
- Preliminary Design/Permitting/ROW
 - March 2024 to April 2025
- Final Design
 - May 2025 to September 2025
- Bid Phase
 - November 2025
- Construction
 - Fall 2026



FEEDBACK/COMMENTS?



THANK YOU

Josif Bicja, PE / Katelyn Welch, PE 

(603) 460-5147 / (603) 460-5601 

jbicja@hoyletanner.com / kwelch@hoyleanner.com 

www.hoyletanner.com 

